



TOWN OF CONWAY
Fornier Rd Pickleball Courts
Project Scope

March 26, 2026

- Supply and install approx. 160-lin. feet of 8-foot chain link fencing. Fencing to have 3-inch terminal posts, 1 1/2-inch line posts, 1 5/8-inch top rail and 2-inch x 9 gauge vinyl coated fabric.
- Supply and install approx. 330-lin. feet of divider netting to connect end fencing and additional divider netting running the width to divide area in half.

- Supply and install 4 sets of pickleball net posts sleeved in concrete footings
- Supply and install 4 sets of pickleball nets

- Total area to receive 1 coat of acrylic re-surfacer.
- Total area to receive 2 coats of deco color acrylic coatings. Top coat to contain proper amount texture to provide a tough wearable surface and proper amount of pigment to give a long lasting and attractive surface. Color to be determined by owner.
- Apply 4 sets of hand painted regulation, acrylic, white textured pickleball lines.

- ** All labor costs to comply with Massachusetts Prevailing Wage laws.

For questions please email together townadmin@conwayma.gov and parksandrec@conwayma.gov.